

한진-부산 신항 STS Crane (Phase 2-1) - 12 Units /Project No. ZP 07-868

Under Progress

Main Particulars

Capacity	Under Spreader : 80 T Under Hook Beam : 100 T		
Span (Rail Gage)	42.67m		
Outreach	70.0 m		
Backreach	20.0 m		
Height of Above Rail	43.0 m		
Height of Below Rail	19.0 m		
Operating Speed	Main Hoist	65T with twin 20ft	70 m/min.
		80T with twin 40ft	90 m/min.
		Empty Spreader	180 m/min.
	Trolley	240 m/min.	
	Gantry	60 m/min.	
	Boom Hoisting Time		5 min.
Motors	Main Hoist	4 x 502 kw 700/1,800 rpm	
	Trolley	450 kw 1,750 rpm	
	Gantry	16 x 36 kw 1,750 rpm	
	Boom Hoist	450 kw 1,750 rpm	
Quantity of Cranes	12 Units		
Date of Delivery	Under Progress		
Etc.	Customer : Hanjin Shipping - 한진 해운(주) Location : Busan Newport (Phase 2-1)		