

현대-부산신항 RMG Crane (Phase 2-2) - 36 Units /Project No. ZP07-910

Under Progress

Main Particulars

| | | | |
|--------------------|--|-----------|--------------|
| Capacity | Single 40.6T | | |
| Span (Rail Gage) | 31m | | |
| Height | Under Spreader 21m | | |
| Operating Speed | Main Hoist | Loader | 40m/min |
| | | No loaded | 80m/min |
| | Trolley | | 120/150m/min |
| Quantity of Cranes | 36 Units | | |
| Date of Contract | 2007 년 | | |
| Date of Delivery | | | |
| Etc. | Customer : Hyundai Shipping - 현대 상선(주) Location : Busan Newport (Phase 2-2) Volume : | | |