

선광 RTGC - 6 Units / Project No. ZP 05 - 708



Main Particulars

Capacity	40.6Ton		
Span (Rail Gage)	23.5m		
Height	17.8m		
Operating Speed	Main Hoist	Loaded	23m/min.
		No loaded	46m/min.
	Trolley		70m/min.
	Gantry		25m/min.(Load) 135m/min.(No load)
Quantity of Cranes	6 Units		
Date of Contract	2005 년		
Etc.	Customer : Sun-Kwang Co., Ltd. Location : 인천 남항 Volume : 1 over 5 & 6+1 configuration		